

FDOT District Four Major Projects


Robert Bostian, PE
District Consultant Project Management Engineer

FDOT District Four Major Projects

- US-1 Bascule Bridge Replacement, Jupiter Inlet
 Palm Beach County Bid Opening March 2021 FM# 428400-2
- SR-710 Beeline Hwy Reconstruction/Widening
 Palm Beach County Bid Opening July 2021 FM# 419251-1
- SR A1A North Causeway Bridge Replacement
 St. Lucie County Bid Opening Sept 2021 FM# 429936-2
- SW 10th Street & I-95 Direct Connector

 Broward County Bid Opening July 2022 FM# 439891-1 & FM# 436964-2

Project Locations




Project milestones reflected in the presentation are subject to change; they are based on current project schedules and funding.


- Bridge Length 915 ft
- Roadway Reconstruction − 2,470 ft
- Full closure with detour
- Intersection improvements and ITS along detour route
- Innovations included
 - Pre-detour work
 - Hybrid-phased construction Commission half of new bridge during detour
 - Precast elements for bascule pier footing
 - □ Preassembly of bascule leaves
 - □ Simplified machinery and electrical installation

Location Map




- Intersection improvements along detour route
- Mitigate community impacts during detour
- New ITS features along detour route








Proposed Typical Sections





Twin Double Leaf Bascule Span



SR 5/US-1 Federal Highway Bridge Twin Double Leaf Bascule Span



Project Status/Schedule



- Design-Bid-Build Project
- Current Estimate \$133 Million
- FDOT PM Bing Wang
- Project Website: https://www.fdot.gov/projects/jupiterus1bridge/main


Project Location Map

SR 710 Beeline Highway Reconstruction / Widening

- SR 710 Roadway Reconstruction 3.1 miles
- Northlake Blvd Roadway Reconstruction - 4000 ft.
- Turnpike Bridge Length 320 ft.
 10 Lanes (180 ft. wide) Pre-Stress Concrete
- Lighting, Mast Arm Signalization, Closed Drainage System with Ponds, and Railroad Crossing



SR 710 / Beeline Highway




SR 710 / BEELINE HIGHWAY
PROPOSED TYPICAL SECTION
FROM NORTHLAKE BLVD. TO BLUE HERON BLVD.





Partial Continuous Flow Intersection

- The partial continuous flow intersection will direct vehicles turning left from SR 710 / Beeline Highway to Northlake Blvd. away from the main intersection to relieve congestion
- U-turn movements introduced for left turn movements:
 - WBL from Northlake Blvd. to SB SR 710
 - o SBL from SR 710 to EB Northlake Blvd.
- Innovative drainage design
- Reduces RW impacts



Partial Continuous Flow Intersection





SR 710 – Beeline Highway

Project Status/Schedule



- Design-Bid-Build Project
- Current Estimate \$107 Million
- FDOT PM Donovan Pessoa

Location Map



SR A1A North Bridge Over ICWW Channel Vertical Clearance




- Bridge Length 4150 ft.
 - o Replacement of structurally and functionally deficient Bridge.
 - o 85 ft. Channel Clearance w/ 300 ft. Observation Deck



- Roadway Reconstruction
 - Juanita Ave Extension 520 ft. New Construction
 - Marina Access Rd. 560 ft. New Construction
 - Old Dixie Hwy 2000 ft. Reconstruction
 - Sunny Lane 500 ft. New Construction
 - Pedestrian Ramp for East Coast Greenway 800 ft. New Construction
- Lighting, Mast Arm Signalization, Drainage, and Railroad Crossing Gates

Proposed Bridge Typical Section





SR A1A North Bridge


Project Status/Schedule




- Design-Bid-Build Project
- Current Estimate \$76 Million
- FDOT PM Donovan Pessoa
- Website: <u>www.SRA1ANorthBridge.com</u>

SW 10th Street Connector

Regional Importance - 3 Adjacent Studies



SW 10th Street History




System Linkage Need

- Regional Weekday Daily Trip Flows
 - Long distance trips
 - Broward, west of Turnpike to / from Palm Beach, east of I-95 – 51,000 daily trips
 - Palm Beach, west of Turnpike to / from Broward, east of I-95 – 23,000 daily trips



Source: 2016 Origin-Destination Data Streetlight Insight

Looking West on SW 10th Street – Full Depressed Option for Connector Road



- SW 10th Street 2 Miles (3 Alternative)
 - New construction of 4 lane divided local roadway
 - New construction of 4 lane high speed connector road
 - Ingress/Egress ramps between SW 10th and connector road

Looking West on SW 10th Street – Partial Depressed: Depressed Eastbound and Westbound Connector Road




Partial Depressed Alternative – Eastbound Connector Road Depressed



Looking West on SW 10th Street – Partial Depressed: Depressed Westbound Exit Ramp



Looking West on SW 10th Street – Non-Depressed / No Managed Lane Access Alternative



I-95 and SW 10th Street




- Direct Connections to I-95
- Connector Road goes over Military Trail

 Widening to add an Express Lane in each direction and accommodate direct connections



SW 10th Street Connector

Project Status / Schedule



- Design-Build Project
- Current Estimate \$600 Million \$1 Billion
- FDOT PM Robert Bostian
- Website: <u>www.SW10Street.com</u>





Thank You

Questions?