



# FINLEY

2020 FTBA Construction Conference - Ivan Liu, P.E.  
Integrated Design and Construction for Florida Bridges



**FINLEY**  
Engineering Group



©FINLEY Engineering Group

# Presentation Objectives

- FINLEY BrIM Workflow
- Tom Staed Veterans Memorial Bridge
- Wekiva Parkway Signature Segmental Bridge
- SR-826 Okeechobee/Palmetto Expressway Interchange Improvement



# Goals for BrIM Workflow



Analysis



Production



Reality


# FINLEY BrIM Workflow

BrIM = Bridge *Integration* Modeling

Phase 1 → Input of Geometry

Phase 2 → Development of Models

Phase 3 → Assemble Integrated Model



# Veterans Memorial Bridge



2020 FTBA Construction Conference - Ivan Liu, P.E.





# Wekiva Parkway Signature Segmental Bridge



2020 FTBA Construction Conference - Ivan Liu, P.E.


# Okeechobee/Palmetto Expressway Interchange



# BrIM Workflow – Phase 1

BrIM = Bridge *Integration* Modeling


Phase 1 → Input of Geometry






# BrIM Workflow – Phase 1


## Global CAD Geometry in SOFiPlus:




## Geometry in AutoCAD:



## Coordinates to Production:




# BrIM Workflow – Phase 1



# BrIM Workflow – Phase 2 Analysis


BrIM = Bridge *Integration* Modeling

Phase 2 → Development of Models





# BrIM Workflow – Phase 2 Analysis



# BrIM Workflow – Phase 2 Analysis

```
$$$$$$  
$ DOWNSTATION SEGMENTS OF PIER 2 / UPSTATION SEGMENTS OF PIER 3 $  
$$$$$$
```

LET  $\#J = 0$

```
LOOP 9 $#N_DOWN(#SEQ(#I)-1)
```

```
CS #N(##I)*1000+(2*##J+2)*10 TYPE D_1 TITL '2DN/3UP+'
$ THE NEXT LINE IS USED FOR THE ACTUAL ACTIVATION OF EACH GROUP (E
$PIER 2 DOWNSTATION
GRP 2*100+(2*##J+2) ICSI #N(##I)*1000+(2*##J+2)*10 ICSD #N(##I)*1000+
```

```
$PIER 3 UPSTATION
GRP 3*100+(2*#J+1) ICS1 #N(#I)*1000+(2*#J+2)*10 ICSD #N(#I)*1000+(
```

UPDATE STAGE MATRIX (DEFINE CS# IN LOAD ACTION CALCULATED)

$$\text{STC} \# \text{STAGE} \# \text{N} (\# \text{I}) * 1000 + (2 * \# \text{J} + 2) * 10$$

```
STO#STG (#STAGE)      #STAGE
STO#STG 1,1,1,1,1,1,1  #STAGE
```

```
STO#CSD_1(#STAGE)  #STAGE
```

```
STO#CSD_3 (#STAGE) 0
STO#CSD_4 (#STAGE) 0
```

```
STO#CSD_4 (#STAGE) 0
STO#CSD_1 (#STAGE) 0
```

```
STO#CSPS_1(#STAGE) 0
STO#CSPS_2(#STAGE) 0
```

```
STO#CSPS_2(#STAGE) 0
STO#CSPB(#STAGE) 0
```

```
STO#CSZP (#STAGE) 0
```

```
STO#CSCR_1(#STAGE) 0
```

```
STO#CSR_2 (#STAGE) 0
```

```
STO#CSD_7(#STAGE) 0
```

```
STO#CSSL (#STAGE) 0
```

```
STO#CSSL_2(#STAGE) 0
STO#N_STAGE #N_STAGE+1 $STAGE COUNT
```

```
CS #N(#I)*1000+(2*#J+2)*10+1 TYPE D_7 TITL '2DN/3UP FORM TRAVELLER'
$ THE NEXT LINE DEFINES THE FORM TRAVELLER LOAD AND CORRESPONDING
$PIER 2 DOWNSTATION
```



```

IF #J<8
  LC 1*1000+(2*#J+2)*10+1 ICS1 #N(#I)*1000+(2*#J+2)*10+1 ATIL #N(#I), "1000+(2*#J+2)*10 - typical 10M travel"
ELSE
  LC 1*1000+(2*#J+2)*10+1 ICS1 #N(#I)*1000+(2*#J+2)*10+1 ATIL 1250 $REMOVE LOAD AT 8-10D DOWN+ STAGE
ENDIF

```



# BrIM Workflow – Phase 2 Analysis









# BrIM Workflow – Phase 2 Construction

BrIM = Bridge *Integration* Modeling


Phase 2 → Development of Models



# BrIM Workflow – Phase 2 Construction




# BrIM Workflow – Phase 2 Construction







# BrIM Workflow – Phase 2 Construction



# BrIM Workflow – Phase 2 Construction




# BrIM Workflow – Phase 2 Construction






# BrIM Workflow – Phase 2 Construction




# BrIM Workflow – Phase 2 Segment

BrIM = Bridge *Integration* Modeling

Phase 2 → Development of Models





# BrIM Workflow – Phase 2 Segment







# BrIM Workflow – Phase 2 Segment



# BrIM Workflow – Phase 2 Segment





# BrIM Workflow – Phase 2 Segment



REINFORCEMENT QUANTITIES																				
BARMARK	DESCRIPTION	ITEM QTY	SIZE	TYPE	LENGTH	A	B	C	D	E	F	G	H	I	J	K	L	N	O	R
47501a	Bottom Slab Butt	1	#4	13	27'-8 3/4"		26'-6"	8"	8"									71.57	71.57	18.5
47501b	Bottom Slab Butt	1	#4	13	27'-8 1/2"		26'-6"	8"	8"									71.57	71.57	18.5
47501c	Bottom Slab Butt	1	#4	13	27'-8 1/4"		26'-5 3/4"	8"	8"									71.57	71.57	18.5
47501d	Bottom Slab Butt	1	#4	13	27'-8"		26'-5 1/4"	8"	8"									71.57	71.57	18.5
47501e	Bottom Slab Butt	1	#4	13	27'-7 3/4"		26'-5 1/4"	8"	8"									71.57	71.57	18.5
47501f	Bottom Slab Butt	1	#4	13	27'-7 1/2"		26'-5"	8"	8"									71.57	71.57	18.5
47501g	Bottom Slab Butt	1	#4	13	27'-7 1/4"		26'-4 3/4"	8"	8"									71.57	71.57	18.4
47501h	Bottom Slab Butt	1	#4	13	27'-7"		26'-4 1/2"	8"	8"									71.57	71.57	18.4
47501i	Bottom Slab Butt	1	#4	13	27'-7"		26'-4 1/4"	8"	8"									71.57	71.57	18.4
47501j	Bottom Slab Butt	1	#4	13	27'-6 3/4"		26'-4"	8"	8"									71.57	71.57	18.4
47501k	Bottom Slab Butt	1	#4	13	27'-6 1/2"		26'-3 3/4"	8"	8"									71.57	71.57	18.4
47501l	Bottom Slab Butt	1	#4	13	27'-6 1/4"		26'-3 1/2"	8"	8"									71.57	71.57	18.4
47501m	Bottom Slab Butt	1	#4	13	27'-6"		26'-3 1/4"	8"	8"									71.57	71.57	18.4
47501n	Bottom Slab Butt	1	#4	13	27'-5 3/4"		26'-3 1/4"	8"	8"									71.57	71.57	18.4
47501o	Bottom Slab Butt	1	#4	13	27'-5 1/2"		26'-3"	8"	8"									71.57	71.57	18.3
47501p	Bottom Slab Butt	1	#4	13	27'-5 1/4"		26'-2 3/4"	8"	8"									71.57	71.57	18.3
47501q	Bottom Slab Butt	1	#4	13	27'-5"		26'-2 1/2"	8"	8"									71.57	71.57	18.3
47501r	Bottom Slab Butt	1	#4	13	27'-4 3/4"		26'-2 1/4"	8"	8"									71.57	71.57	18.3
47501s	Bottom Slab Butt	1	#4	13	27'-4 1/2"		26'-2"	8"	8"									71.57	71.57	18.3
47501t	Bottom Slab Butt	1	#4	13	27'-4 1/4"		26'-1 3/4"	8"	8"									71.57	71.57	18.3
47501u	Bottom Slab Butt	1	#4	13	27'-4 1/4"		26'-1 1/2"	8"	8"									71.57	71.57	18.3
47501v	Bottom Slab Butt	1	#4	13	27'-4"		26'-1 1/4"	8"	8"									71.57	71.57	18.3




# BrlM Workflow – Phase 2 Segment




# BrIM Workflow – Phase 3 Integrated 3D Model

BrIM = Bridge *Integration* Modeling

Phase 3 → Assemble Integrated Model




# BrIM Workflow – Phase 3 Integrated 3D Model







# BrIM Workflow – Phase 3 Integrated 3D Model



# BrIM Workflow – Phase 3 Integrated 3D Model




# BrIM Workflow – Phase 3 Integrated 3D Model









# BrIM Workflow – Phase 3 Integrated 3D Model





# Asset Management

## Bridge Asset Management:

- As-Built Records
- Repair Procedures
- Inspection Notes



# 3D Proof Models





# Closing Remarks



Why is BrIM better? Efficient, Integration, and Visualization!



# Questions?




Ivan Liu, P.E.  
Bridge Engineer

1589 Metropolitan Boulevard | Tallahassee, FL 32308-3776 USA  
+1 (850) 894-1600 Office | +1 (850) 274-2387 Cell  
[Ivan.Liu@finleyengineeringgroup.com](mailto:Ivan.Liu@finleyengineeringgroup.com) | [www.finleyengineeringgroup.com](http://www.finleyengineeringgroup.com)



## Tallahassee Location:

1589 Metropolitan Boulevard  
Tallahassee, FL 32308-3776 USA  
Phone: +1-850-894-1600  
Fax: +1-850-894-1614



## Prague Location:

Na Morani 1750/4  
Prague 2 – Nove Mesto, 12800  
Czech Republic  
Phone: +420-222-580-074

