



December 22, 2017

Design Memorandum No. 2017.13

TO: All DPW Engineering and Construction Staff, and Consultants

**THRU: Melody Park, PE
Chief Engineer
Department of Public Works**

**FROM: Mark H. Zwoyer, PE
Administrator – Engineering Design
Department of Public Works**

RE: Pay Items for Contracts Bid by the City

EFFECTIVE: January 1, 2018

The Department of Public Works (DPW) is working to standardize pay items used in association with City let construction contracts. DPW generally uses Indiana Department of Transportation (INDOT) pay items. Pay items that do not appear in the INDOT lists will be assigned DPW item codes. Item codes shall now be listed on the BID-3 forms in the contract documents; a sample BID-3 is attached.

DPW is developing a process to identify pay items typically used and to assign them DPW item codes. In the meantime, use the following naming convention for pay items not found on INDOT lists:

- The form is D-xxx-nnnnn
- xxx is the INDOT Standard Specification section where the pay item would fit

- nnnnn is the line number from BID-3 for now. A DPW catalog is anticipated by mid-2018

DPW pay items require an accompanying technical specification. The technical specification shall follow INDOT requirements for special provisions.

PART 3
CONTRACT ITEMS AND UNIT PRICES
Project No. RS-16-005
Resurfacing in Marion County Area No.7

LINE NO.	ITEM CODE	ITEM DESCRIPTION	UNITS	QUANTITY	UNIT PRICE	TOTAL PRICE FOR ITEM
1	105-06845	CONSTRUCTION ENGINEERING	LS	1		
2	110-01001	MOBILIZATION AND DEMOBILIZATION	LS	1		
3	201-52370	CLEARING RIGHT OF WAY	LS	1		
4	D-201-00004	CURB, CONCRETE, REMOVE (ALL TYPES)	LFT	375		
5	D-201-00005	SIDEWALK CONCRETE, REMOVE (ALL TYPES)	SYS	183		
6	202-02240	PAVEMENT REMOVAL	SYS	805		
7	D-203-00007	GRADE AND COMPACT MILLINGS	SYS	5391		
8	D-203-00008	GRADING, MAINLINE	LFT	2014		
9	205-06933	TEMPORARY INLET PROTECTION	EA	75		
10	301-12234	COMPACTED AGGREGATE NO 53	TON	386		
11	306-08034	MILLING, ASPHALT, 1 1/2 IN.	SYS	38898		
12	306-08041	MILLING, PCCP, 3 1/2 IN.	SYS	4573		
13	306-08595	MILLING, ASPHALT, 3 1/2 IN.	SYS	76895		
14	402-07452	HMA WEDGE AND LEVEL, TYPE C	TON	126		
15	D-402-00015	HMA, SURFACE, TYPE B, 9.5 mm	TON	209		
16	D-402-00016	HMA, INTERMEDIATE, TYPE B, 19.0 mm	TON	92		
17	D-402-00017	HMA, SURFACE, TYPE C, 9.5 mm	TON	8996		
18	D-402-00018	HMA, INTERMEDIATE, TYPE C, 19.0 mm	TON	9247		
19	D-402-00019	HMA, BASE 25.0 mm, FOR BASE REPAIRS, TYPE C	TON	1816		
20	D-402-00020	HMA, BASE 25.0 mm, FOR BASE REPAIRS, TYPE C, UNDISTRIBUTED	TON	239		
21	506-06333	PCCP PATCHING, FULL DEPTH	SYS	1424		
22	604-06070	SIDEWALK, CONCRETE	SYS	83		
23	604-08086	CURB RAMP, CONCRETE	SYS	93		
24	605-06140	CURB AND GUTTER, CONCRETE	LFT	197		
25	D-605-00025	CURB, CONCRETE (ALL TYPES)	LFT	359		
26	610-07488	HMA FOR APPROACHES, TYPE C	TON	924		
27	621-06574	SODDING	SYS	281		
28	720-01355	INLET, CLEAN EXISTING	EA	23		
29	720-44000	CASTING, ADJUST TO GRADE	EA	24		
30	D-720-00030	REMOVE AND RESET CASTING TO GRADE	EA	1		
31	801-06640	CONSTRUCTION SIGN, TYPE A	EA	93		
32	801-06775	MAINTAINING TRAFFIC	LS	1		
33	D-805-00033	DETECTOR LOOP, CIRCULAR, 6' X 6'	EA	28		
34	D-805-00034	DETECTOR HOUSING, ADJUST TO GRADE	EA	7		
35	808-75340	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, R X R	EA	2		
36	808-06701	LINE, THERMOPLASTIC, BROKEN WHITE, 4 IN	LFT	350		
37	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN	LFT	50962		
38	808-75297	TRANSVERSE PAVEMENT MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN	LFT	1201		
39	D-808-00039	TRANSVERSE MARKING, THERMOPLASTIC, YIELD LINE, WHITE, 18 IN	LFT	28		
40	808-75300	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 6 IN	LFT	1001		
41	808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN	LFT	2408		
42	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	LFT	58459		
43	808-75320	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC LANE INDICATION ARROW	EA	33		
44	808-75325	PAVEMENT MESSAGE MARKING, THERMOPLASTIC ONLY	EA	17		
45	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKERS, BLUE, TWO WAY	EA	50		
46	202-94810	CURB TURNOUT, REMOVE	EA	1		
47	605-09137	CURB, TURNOUT	EA	1		
48	616-06405	RIPRAP, REVETMENT	TON	3		
49	D-616-00049	GEOTEXTILES	SYS	7		
50	D-801-00050	SIGN ASSEMBLY, RELOCATE	EA	3		
51	D-615-00051	HARRISON MONUMENT, RESET	EA	10		

52	D-615-00052	MARION COUNTY SURVEYORS OFFICE REIMBURSEMENT	EA	10	\$500.00	\$5,000.00
----	-------------	----------------------------------------------	----	----	----------	------------

TOTAL BID AMOUNT (IN FIGURES)

(IN WORDS)