



Kentucky River Lock and Dam Projects

Daniel A. Gilbert, PE
April 29, 2011
KSPE Annual Conv.



Lock and Dam No. 1



Lock and Dam No. 9

One Team. Infinite Solutions.




Presentation Overview

- General Information
- History
- Existing Conditions
- Recent Projects
- Why Cell Dams?
- Dam Construction
- Lessons Learned



Dam No. 3

Kentucky River Basin



- 255 Miles of Main Stem
- 42 Counties
- 14 Locks and Dams

Navigation


- Locks 1 – 3 – Restricted Use
- Lock 4 – Seasonal Operation
- Locks 5–9 and 11-14 – Cutoff Walls



Lock 4

Ownership and Operation

- KRA Established in 1986
- Lock and Dams 1-4
 - USACE Owned
 - KRA Leased and Maintained
- Lock and Dams 5-14
 - KRA Owned and Maintained




Kentucky River Users

- Tier I
 - Over 780,000 Households
 - 2¢ per 1,000 Gallons
 - Fund KRA Base Operations
- Tier II
 - 11 Municipal Water Suppliers
 - 9 Business Entities
 - 6¢ per 1,000 Gallons
 - Fund Capital Projects



Kentucky River Lock and Dam History

- Original Construction
1836 to 1917
- 19th Century
Commerce




Lock Wall Construction


- Locks 1 - 8
 - Masonry Construction



Lock 6





Lock 7



Lock Wall Construction


- Locks 9 – 14
 - Concrete Construction




Dam Construction

- Dams 1 - 8
 - Rock-filled Timber Crib


Dam No. 4



Lock and Dam No. 2




Lock and Dam No. 3



Dam Construction


- Dams 9 – 14
 - Concrete Construction



Dam No. 9


Typical Dam Repairs

- Concrete Capping



Typical Dam Repairs

- Concrete Capping



Typical Dam Repairs




■ Sheet Pile Facing

Sheet Piling





Timber Cribbing

Cutoff Walls



Existing Conditions

- 2007 Assessment of Lock and Dams
 - Identify Deficiencies
 - Above and Below Water Inspections
 - Historical Review
 - Prioritize Repairs
 - Risk-based Analysis
 - Conceptual Designs



Assessment Findings

- Deficiencies Observed at each Facility
- Facilities Have Outlived Design Service Life
- Highest Priority Elements
 - Far Abutments
 - Dams
 - Upper Lock Gates
 - Downstream Training Walls
- No Imminent Failures Indicated by Observations



Final Report
Assessment Study for Kentucky
River
Dam Nos. 1-8 and 11-14
Various Counties, Kentucky

Prepared for:
Kentucky River Authority
Frankfort, Kentucky
October 16, 2008


Typical Deficiencies

- Lack of Derrick Stone
- Downstream Toe Undermining
- Timber Crib Section Loss
- Missing Apron Sections
- Signs of Instability in Walls
- Concrete in Poor Condition
- Deteriorating Sheet Piling
- Deteriorating Lock Gates



Recent Lock and Dam Projects

- Lock and Dam No. 9
 - \$14.7M
 - 2007 – 2010
- Lock and Dam No. 3
 - \$13.8M
 - 2009 - 2011



Lock and Dam No. 9

Key People

Owner (Finance and Admin. Cabinet)



Using Agency



Contractors

LD9




Engineer

LD3



LD9 - Existing Conditions


- Structures do not meet Current Stability Criteria
- Long Term Prognosis is Poor




LD9 – Project Design Goals

- Meet Current Design Criteria
- 50 Year Design Life
- Preserve Lock Walls
- Preserve Hydraulic Signature
- Accommodate Future Crest Raise
- Accommodate Pool 8 Mining
- Include Water Conveyance System (WCS)

Crest Raise, Pool Mining, and WCS




Crest Raise, Pool Mining, and WCS



Crest Raise, Pool Mining, and WCS

Siphon Pipes over Dam - 3 pipes
@ approx. 23 cfs (max) each



LD9 Pre-Construction Conditions

Jessamine Co.

Flow

Dike

450 ft +/-

Auxiliary Dam


Lock

Main Dam

Madison Co.

Photo from GRW Aerial Surveys (2001)

LD9 – Construction Plan





LD9 – Completed Construction



LD3 - Existing Conditions

- Absence of Derrick Stone
- Downstream Undermining of Spillway
- Missing or Damaged Sections of Apron
- Partial Collapse of Stone Abutment
- Concrete in Poor Condition
- Structures do not meet Current Stability Criteria
- Long Term Prognosis is Poor




LD3 – Project Design Goals


- Meet Current Design Criteria
- 50 Year Design Life
- Preserve Lock for Operation
- Preserve Hydraulic Signature
- Accommodate Future Crest Raise
- Rehabilitate Lock Nos. 3 & 4 (Design)




LD3 – Pre-Construction Conditions



LD3 – Construction Plan




LD3 – Current Construction Progress



Upcoming Projects

- Dam No. 8
- 2011 - 2014
- Lock Nos. 1-4
- 2012



Why Cell Dams?

- Similar to Cofferdams and Mooring Cells (“In-the-Wet”)
- Filled with Concrete
- Simple, Flexible Construction
- Commonly Used on Run of the River Dams



Green River




Muskingum River

Why Cell Dams?



- River Volatility

- Pool can quickly rise and fall 5 to 10 feet several times per year.
- Contractor Risk Driver
- Strong Consideration in Approach Evaluation
- Affects Effective Height of Cofferdams



Why Cell Dams?

- Cofferdams
 - Staged Construction
 - In-depth Analysis
 - Effective Height
 - Maintain Dewatered Condition



Example Staged Cofferdam Scheme

Volatility of the Kentucky River - Example

- At Lock and Dam 9, typically 0-2 feet of water going over the dam.
- May 2, 2010, 8AM = 5.6 ft over the dam
- May 2, 8PM = 24.6 ft over the dam
- May 3, 8AM = River crested at 31 ft over the dam



Contractor staging area is about 22 feet above crest of LD9



Contractor staging area is about 22 feet above crest of LD9

River crested about 31 feet above crest of LD9




Why Cell Dams?

- Dewatering
 - Difficulties with Karst Geology
 - Feasible?
 - Undetermined prior to Construction
 - May Need Grouting Program
 - Increased Risks to Contractor
 - Increased Risks to Owner
 - Increased Costs
- In-the-Wet Approach Avoids Need to Dewater



Dewatering at LD9



Foundation Cell Inspection for LD9

Why Cell Dams?

Advantages

- Reduced construction footprint
- Reduced environmental impacts
- Cost and schedule savings
- Reduced risks to contractor
- Reduced risks to owner
- Accommodate irregular rocklines
- Reduced karst geology risks
- Suitable for volatile rivers

Disadvantages

- Underwater diver work
- More difficult quality assurance
- Dam geometry not optimized
- Underwater concrete placement

Dam Construction

- Concrete-filled Cellular Sheet Pile Structures w/ Connecting Arc Cells
- Pre-Dredge
- Set Template
- Drive Sheet Piling
- Cell Cleanout
- Concrete
- REPEAT



Lock and Dam No. 9

Sheet Pile Template



07/05/2007 01:07 PM

Sheet Piling Installation



Cell Cleanout - Dredging




A Bit of History



A Bit of History

The Circle R brand indicates the owner was the W. J. Roberts Company of Frankfort.




Cell Cleanout - Airlifting



Cell Cleanout - Diver Work



Contractor Risks – High Water Events




Cell Infill Placement – “In-the-Wet”


Gravity Method



Pump Method




Tremie Concrete Placement




Tremie Concrete Placement


▪ Bulging Flow Pattern



▪ Layered Flow Pattern



Concrete Laitance




Underwater Concreting


Couple of Things to Consider.....

- Concrete Mix & Admixtures
- Placement Plan
 - Gravity Method
 - Pump Method
- Rate of Rise
- Retardation Time
- Tremie Layout/Sequencing
- QA/QC
- Demonstration Placement

Requires Detailed Concreting Plans!



Cap Concrete Placement




Abutments/Tie-ins


“The hard parts”

- External Soil Loads
- Account for Scour
- Geometric Constraints / Interaction with other Structures
- Risk of Flanking (During Construction and Long Term)
- Seepage & Piping (Around or Through)
- Pareto Principal (80-20 Rule) in Effect During Design

LD3 – East Abutment



LD3 – Lock Wall Tie-in



Lessons Learned

- Construction Delays
 - How Are They Evaluated/Regulated?
 - River Elevations
 - Set Workdays
 - Realistic Construction Schedules
 - Take into Account Historical Hydrographs
- Damages from Elevated River Conditions
- Rockline Adjustments
- Unit Prices for Potential Additional Work Items


Lessons Learned

- Detailed Submittal Process
 - PE Stamp for All Calculations
 - Assures Contractor has Specific Approach
 - Engineer/Owner Opportunity to Review
- Construction Sequence/Restrictions
 - Protect Pool
 - Spell Out Very Clearly

Lessons Learned

- Concreting
 - Demonstration Placements
 - Concrete Retardation Durations
 - “Work Out the Bugs”
 - Prepare Contract Documents for Gravity and Direct Pumping Concrete Placement Methods
 - QA/QC Measures
 - Confirmation Coring
 - Good Documentation
 - Investigate if Questions Exist

Lessons Learned



Lessons Learned



Lessons Learned



Questions?

- References

- Leiland R. Johnson, “The Falls City Engineers”, 1984
- “Assessment of Underwater Concrete Technologies for In-the-Wet Construction of Navigation Structures”, USACE, 1999.
- KRA Website
 - <http://finance.ky.gov/ourcabinet/attachedagencies/kra.htm>
- “Assessment Study for KY River Dam Nos. 1-8 and 10-14”, Stantec, 2007.
- Technical Report INP-SL-1, USACE, September 1999.